


**Project  
RoU Verification  
Report**

2022

COVER PAGE	
RoU Project Verification Report Form (VR)	
BASIC INFORMATION	
Name of approved UWR Project Verifier / Reference No.	Enviance Services Private limited
Type of Accreditation	<input checked="" type="checkbox"/> RoU Accreditation UWR <input type="checkbox"/> Water Audit/Water Footprint Expertise
Approved UWR RoU Scopes for Project Verification	RoU Scope 5: Conservation measures taken to recycle and/or reuse water, spent wash, wastewater etc. across or within specific industrial processes and systems, including wastewater recycled/ reused in a different process, but within the same site or location of the project activity. Recycled wastewater used in off-site landscaping, gardening or tree plantations/forests activity are also eligible under this Scope.
Validity of UWR approval of Verifier	30/09/2027
Completion date of this VR	10/12/2024
Title of the project activity	ETP wastewater Treatment by Gangamai Industries & Constructions Ltd
Project reference no. (as provided by UWR RoU Program under Approved for Verification tab)	UWR ID: 463
Name of Entity requesting verification service (can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	Vивиid Emissions Reductions Universal Pvt. Ltd. Name: Lokesh Jain Email ID – lokesh.jain@viviidgreen.com
Contact details of the representative of the Entity, requesting verification service (Focal Point assigned for all communications)	Vивиid Emissions Reductions Universal Pvt. Ltd. Name: Lokesh Jain Email ID – lokesh.jain@viviidgreen.com
Country where project is located	India

<b>Applied reference documents used for estimation</b> (approved water data and reference guides under the UWR RoU Standard used)	Water Data Guide
<b>Project Verification Criteria:</b> Mandatory requirements to be assessed	<input checked="" type="checkbox"/> UWR Standard <input checked="" type="checkbox"/> Applicable Approved Calculations <input checked="" type="checkbox"/> Applicable Legal requirements /rules of host country <input checked="" type="checkbox"/> Eligibility of the Project Type <input checked="" type="checkbox"/> Start date of the Project activity <input checked="" type="checkbox"/> Meet applicability conditions in the applied methodology <input checked="" type="checkbox"/> Credible Water Data Sets <input checked="" type="checkbox"/> Do No Harm Test <input checked="" type="checkbox"/> RoU calculations <input checked="" type="checkbox"/> PCNMR <input checked="" type="checkbox"/> No Double Counting <input type="checkbox"/> Others (please mention below)
<b>Project Verification Criteria:</b> Optional requirements to be assessed	<input checked="" type="checkbox"/> Environmental Safeguards Standard and do-no-harm criteria <input checked="" type="checkbox"/> Social Safeguards Standard do-no-harm criteria
<b>Project Verifier's Confirmation:</b> The <i>UWR Project Verifier</i> has verified the UWR project activity and therefore confirms the following:	<p>The UWR RoU Project Verifier [<i>Enviance Services Private Limited</i>], certifies the following with respect to the UWR Project Activity [<i>ETP wastewater Treatment by Gangamai Industries &amp; Constructions Ltd</i>].</p> <p><input checked="" type="checkbox"/> The Project Owner has correctly described the Project Activity in the PCNMR version 2.0 (dated 25/11/2024) including the applicability of the guidance documents and water data as outlined in the UWR RoU Standard [<i>RoU Scope 5: Conservation measures taken to recycle and/or reuse water, spent wash, wastewater etc. across or within specific industrial processes and systems, including wastewater recycled/ reused in a different process, but within the same site or</i></p>

	<p>location of the project activity. Recycled wastewater used in off-site landscaping, gardening or tree plantations/forests activity are also eligible under this Scope] and meets the applicability conditions and has achieved the estimated RoUs, complies with the monitoring methodology and has calculated RoU estimates correctly and conservatively.</p> <p><input checked="" type="checkbox"/> The Project Activity is likely to generate 569,135 RoUs as indicated in the PCNMR version 2.0, which are applicable with UWR rules</p> <p><input checked="" type="checkbox"/> The Project Activity is not likely to cause any net-harm to the environment and/or society</p> <p><input checked="" type="checkbox"/> The Project Activity complies with all the applicable UWR rules<sup>1</sup> and therefore recommends UWR Program to register the Project activity with RoUs.</p>
<b>Project Verification Report, reference number and date of approval</b>	<p>Verification Report UCR Project ID: 463</p> <p>Date: 11-12-2024</p>
<b>Name of the authorised personnel of UWR Project Verifier and his/her signature with date</b>	<p>Vidhya Murali Krishna</p>  <p>Quality Manager</p> <p>Date: 11/12/2024</p>

<sup>1</sup>[https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UWRtermsandconditionsVer6\\_171023134009203288.pdf](https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UWRtermsandconditionsVer6_171023134009203288.pdf)

## ❖ PROJECT VERIFICATION REPORT

### ❖ Executive summary

The project activity is titled – “ETP Wastewater Treatment by Gangamai Industries & Constructions Ltd.”. The project is located in Harinagar, Najik Babhulgaon, Post: Rakshi, Tal-Shevgaon, Dist: Ahmednagar, Maharashtra, India.

Company's Name	Plant Treatment Capacity (m <sup>3</sup> /d)	Commissioning Date		Location	Geo co-ordinates of Location
Gangamai Industries and Constructions Limited (GIACL)	Installed capacity = 1000 m <sup>3</sup> /d (1 MLD)  Operational capacity = 563 m <sup>3</sup> /d (0.563 MLD)	ETP	10/12/2013	Harinagar, Najik Babhulgaon, Post: Rakshi, Tal-Shevgaon, Dist: Ahmednagar, Maharashtra, India	19°22'47.28" N & 75°17'00.72" E

The project activity includes Gangamai ETP, Gangamai Industries and Constructions Limited (GIACL), Harinagar, Najik babhulgaon, Taluka Shevgaon, District Ahmednagar (M.S.) is one of the companies of Padmakar Mulay Group of Companies, Aurangabad and is into the manufacturing of sugar & production and marketing of Distillery & Ethanol.

Considering the sugarcane availability in the factory area, the company had established a 2500 TCD Sugar Plant and started crushing operations from January 2001 onwards at Harinagar, Post. Ghatnandra, Ta. Sillod, Dist. Aurangabad, Maharashtra, Pin code- 431 113. Thereafter, Ethanol Plant and Distillery Plant both 30 KLPD were established and put in operations in June 2004 and April 2007 respectively.

GIACL affirms that they meet all the requirements outlined in the management plan regarding ownership, legal rights, permits, and cost details for the successful implementation of the project. Specifically.

**Water User Rights:** GIACL holds the necessary water user rights for the area within the project's boundary. These rights are legally secured and ensure that the GIACL has full entitlement to use the water resources required for the project's operations.

**Legal Land Title:** GIACL holds an uncontested legal land title for the entire project area within the project's boundary. The title is fully documented and free of any disputes, confirming the GIACL's legal right to utilize the land for project purposes.

**Necessary Permits:** GIACL has obtained all the required permits for the implementation of the project. In cases where certain permits are pending, GIACL has already applied for the necessary approvals and is working in full compliance with the relevant regulatory requirements to ensure the timely commencement of the project.

Cost Details: GIACL has thoroughly assessed and documented the cost details for project implementation. A detailed cost breakdown is available, covering all aspects of project development, including infrastructure, permits, equipment, and operational costs.

GIACL has installed 1MLD Effluent Treatment Plant (ETP) on 10 Dec'2013 to treat and recycle the wastewater generated from the production process. The operational capacity of the plant is 0.563 MLD. By treating and reusing wastewater, the company can contribute to environmental conservation and reduce soil contamination. The Total Water requirement for Sugar Factory is 3550 M<sup>3</sup>/Day. Out of which 527 M<sup>3</sup>/Day would be the fresh water from Jayakwadi Dam on Godavari river and remaining is 3023 M<sup>3</sup>/Day (condensate water- 3006 M<sup>3</sup>/Day + Rain water Harvesting- 17 M<sup>3</sup>/Day).

The sugar industry generates a significant amount of wastewater from various stages of production process, which contains high levels of pollutants such as organic matter, suspended solids, and various chemicals. The process includes water used for cane washing, which cleans the sugarcane before processing, and juice extraction, where water is utilized in the milling process to extract juice from the cane. During boiling and crystallization, water is employed to concentrate the juice and form sugar crystals. Additionally, water is used in cooling and condensing to cool and condense vapours during the boiling process. Finally, cleaning and maintenance activities within the factory premises also contribute to wastewater generation, as water is used to clean equipment and maintain hygiene standards.

If the wastewater is released into the environment without proper treatment, it can cause severe pollution, affecting aquatic life, soil quality, and human health.

Therefore, this project activity helps reduce the environmental impact by treating wastewater and utilizing it for Gardening and agricultural purposes such as Irrigation, further promoting sustainability.

The project activity qualifies under the UCR RoU program since the PP has undertaken water conservation measures to recycle and reuse Industrial wastewater. Industrial Wastewater is a highly potential source of water for various purposes and is highly underutilized in the country. All the water quality reports are in line with the Maharashtra Pollution Control Board (MPCB).

The current monitoring period is from 01/01/2014 to 31/12/2023 and the RoU's generated by the project activity in this monitoring period are 569,135 RoU's.

### **Scope of Verification**

The scope of the services for the project is to perform Project Verification of concerned Project Activity. The scope of verification is to assess the claims and assumptions made in the Project Concept Note & Monitoring Report (PCNMR) against the UWR criteria, including but not limited to, UWR program verification guidance document, UWR Standard, UWR Program Manual, and related rules and guidelines established under Program process.

### **Verification Process and Methodology**

The verification process was undertaken by a competent verification team and involved the following,

- Desk review of documents and evidence submitted in context of the reference rules and guidelines issued by UWR,
- Undertaking/conducting site visit/remote audit, interview or interactions with the representative of the project owners/representatives,
- Reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate and preparing a draft verification opinion based on the auditing findings and conclusions
- Finalization of the verification opinion (this report)

### **Desk/Document review**

A detailed desk review of the PCNMR, Methodology and all other associated documentation and references took place in advance of the remote site visit, and additional documents that were not available for the desk review were requested for review during the remote site visit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face to face interviews with key stakeholders (including the project developers and where necessary, government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included below in Appendix 3.

### **Follow up interviews/site visit**

The verifier conducted remote audit and had requested for site photographs, short videos. A remote interview was conducted with the project owners and stakeholders.

### **Conclusion**

Based on the work performed, the verifier concludes that the “ETP Wastewater Treatment by Gangamai Industries & Constructions Ltd.”. The information and data presented in the PCNMR version 2.0 dated 25/11/2024 meets all relevant requirements of the UWR for UWR project activities.

For the current monitoring period, verified RoU's achieved by the project activity were as below;

Start date of monitoring period	01/01/2014
End date of monitoring period	31/12/2023
RoU's achieved	569,135 RoU's

❖ **Project Verification team, technical reviewer and approver**

### Project Verification team

No.	Role	Last name	First name	Affiliation (e.g. name of central or other office of UWR Project Verifier or outsourced entity)	Involvement in		
					Document review	Off-Site inspection	Interviews
1.	Team Leader/ Technical Expert	Kumar	Pankaj	Enviance Services Private Limited	Yes	Yes	Yes
2.	V-V Trainee / Technical Expert in Trainee	Jain	Vipul	Enviance Services Private Limited	Yes	Yes	Yes
3.	V-V Trainee / Technical Expert in Trainee	Mahajan	Swati	Enviance Services Private Limited	Yes	Yes	Yes

### Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation (e.g. name of central or other office of UWR Project Verifier or outsourced entity)
1.	Technical reviewer	Internal	-	Vijayanand	Contractual resource

## ❖ Means of Project Verification

### Desk/document review

❖ A detailed desk review of the PCNMR, methodology and all other associated documentation and references took place in advance of the remote audit, and additional documents that were not available for the desk review were requested for review during the remote audit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face-to face interviews



with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

❖ A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

### Off-site inspection

**Date of off-site inspection:**  
28/11/2024

No.	Activity performed Off-Site	Site location	Date
1.	<ul style="list-style-type: none"> <li>a) An assessment of the implementation and operation of the project activity as per the PCNMR and UWR requirements</li> <li>b) Verification of the project design, as documented is sound and reasonable, and meets the identified criteria of UWR Standard Requirements and associated guidance</li> <li>c) Assessment to conformance with the certification criteria as laid out in the UWR Standards;</li> <li>d) Evaluation of the conformance with the certification scope, including the water project and baseline scenarios, additionality; scopes of water project; and the physical infrastructure, activities, technologies and processes of the water project to the requirements of the UWR;</li> <li>e) Evaluation of the calculation of RoU's, including the correctness and transparency of formulae and factors used; assumptions related to estimating RoU's.</li> <li>f) Review of information flows for generating, aggregating and reporting of the parameters to be monitored</li> <li>g) To confirm that the operational and data collection procedures can be implemented in accordance with the Monitoring Plan</li> <li>h) Cross-check of information provided in the submitted documents and data from other sources available at site</li> <li>i) Review of calculations and assumptions made in determining RoU's, and an identification of QA/QC procedures in place to prevent, or identify and correct, any errors or omissions in the reported monitoring parameters</li> <li>j) Interviews of local Stakeholders</li> </ul>	Harinagar, Najik Babhulgaon, Post: Rakshi, Tal-Shevgaon, Dist: Ahmednagar, Maharashtra, India	28/11/2024

## Interviews

No.	Interview			Date	subject
	Last name	First name	Affiliation		
1.	Khedekar	-	Gangamai Industries and Constructions Limited (GIACL)	28/11/2024	Project Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country requirements, RoU calculations Project implementation, monitoring, Local stakeholder consultation
2.	Kharde	G.N.			
3.	Ghule	-			
4.	Mahanta	Sarashi	Viviid emissions reductions universal private Ltd		
5.	Mehta	Agrah			
6.	Mulay	Padmakar	Local stakeholders		
7.	Mulay	Ranjeet P.			
8.	Khedekar	Vishnu S.			

## Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
<b>Rainwater Offset Units or Water Credits (RoU)</b>			
Identification and Eligibility of project type	-	-	-
General description of project activity	03	-	-
Application and selection of methodologies and standardized sets	-	-	-
- Application of RoU methodologies and standardized data sets	-	-	-
- Deviation from methodology and/or methodological tool	-	-	-
- Clarification on applicability of methodology, tool and/or standardized data sets	-	-	-
- Project boundary and unutilized water sources	-	-	-
- Likely scenario without RoU Project	-	-	-
- Estimation of RoUs	01	01	-
- PCNMR	02	-	-
Start date, crediting period and duration	-	-	-
Positive environmental impacts on water table and/or groundwater recharge and/or water security in the area	-	-	-
Project Owner- Identification and communication	-	-	-
Others (please specify) Positive social impacts	02	01	-
<b>Total</b>	<b>08</b>	<b>02</b>	

## ❖ Project Verification findings

### Identification and eligibility of project type (Approved Project Activities (Positive List))

<b>Means of Project Verification</b>	<p>The project is an effluent treatment plant with installed treatment capacity of 1000m<sup>3</sup>/day (1 MLD) and operational capacity of 563 m<sup>3</sup>/day (0.563 MLD). This is confirmed based on the commissioning certificate, operational capacity document and technical specifications.</p> <p>Since the project is a effluent treatment plant which recycles and reuses industrial wastewater it comes under scope 5 project as per UWR Rainwater (RoU) Standard, version 7.0 (<a href="https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com//Documents/RainWaterOffsetStandardver7_130824144129526582.pdf">https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com//Documents/RainWaterOffsetStandardver7_130824144129526582.pdf</a>)</p> <p>The Project owner has used valid PCNMR form available at the UWR website for the preparation of PCNMR for the current project activity. The project has prepared PCNMR in line with UWR guidance and requirements.</p>
<b>Findings</b>	No findings raised
<b>Conclusion</b>	<p>The UWR-approved format is used for description and the project meets the requirement of the UWR RoU verification standard version 2.0 and UWR RoU standard version 7.0. UWR project communication agreement was submitted to the verifier and the same has been verified. Methodology referenced and applied appropriately describing the project type. The eligibility of the project aggregator is verified using the UWR communication agreement, project correctly applies the verification standard, UWR project standard, and UWR regulations. The project activity is overall meeting the requirements of the UWR Verification standard and UWR project standard.</p>

### General description of project activity

<b>Means of Project Verification</b>	<p>The project is an effluent treatment plant with installed treatment capacity of 1000m<sup>3</sup>/day (1 MLD) and operational capacity of 563 m<sup>3</sup>/day (0.563 MLD) and its commissioning date is verified through the commissioning certificate of the project. The documents confirm the treatment of wastewater from the sugar industry in this project.</p> <p>Assessment team conducted documentation review of the PCNMR against the UWR RoU verification standard version 2.0 and UWR RoU standard version 7.0 and the UWR-PCNMR-FORM Version 3.0.</p> <p>By checking the supporting documents, it is confirmed that the project is an effluent treatment plant, the project is located in Harinagar, Najik babhulgaon, Taluka Shevgaon, District Ahmednagar, Maharashtra state of India. The approximate geo-coordinates of the project locations are mentioned below.</p> <table border="1" data-bbox="619 810 1406 1037"> <tr> <th>Plant Treatment Capacity (m<sup>3</sup>/d)</th><th>Geo co-ordinates of Location</th></tr> <tr> <td>Installed capacity = 1000 m<sup>3</sup>/d (1 MLD)</td><td>19°22'47.28" N &amp; 75°17'00.72" E</td></tr> <tr> <td>Operational capacity = 563 m<sup>3</sup>/d (0.563 MLD)</td><td></td></tr> </table> <p>Assessment team performed an offsite inspection of project and confirmed that the location described in the PCNMR are accurate.</p>	Plant Treatment Capacity (m <sup>3</sup> /d)	Geo co-ordinates of Location	Installed capacity = 1000 m <sup>3</sup> /d (1 MLD)	19°22'47.28" N & 75°17'00.72" E	Operational capacity = 563 m <sup>3</sup> /d (0.563 MLD)	
Plant Treatment Capacity (m <sup>3</sup> /d)	Geo co-ordinates of Location						
Installed capacity = 1000 m <sup>3</sup> /d (1 MLD)	19°22'47.28" N & 75°17'00.72" E						
Operational capacity = 563 m <sup>3</sup> /d (0.563 MLD)							
<b>Findings</b>	CL 01, CL 02 and CL 04 were raised and closed successfully. More information presented appendix below.						
<b>Conclusion</b>	The description of the project activity is verified to be true based on the review of PCNMR, Commissioning Certificate and other submitted documents.						

#### Application and selection of water data and calculation parameters

<b>Means of Project Verification</b>	<p>Verification criteria is as per the requirements of UWR RoU program for the scope – 5.</p> <p>For applicability mentioned in the PCNMR, commissioning certificates, DPR, technical specifications, flow meter data were checked.</p>
<b>Findings</b>	No findings raised.
<b>Conclusion</b>	The project has effectively implemented the water treatment unit following the guidelines of UWR RoU standards by recycling and reusing the industrial wastewater and has a positive impact of local hydrology and community water resources.

#### Clarification on applicability of tool and/or RoU estimates

<b>Means of Project Verification</b>	The documents reviewed are ETP basics, ensuring proper operation of flow meters, RoU estimates by reviewing the flow details, UWR RoU standard, and UWR RoU Verification Standard.
<b>Findings</b>	No findings raised.
<b>Conclusion</b>	The verification team confirms that all the applicability criteria set by the UWR RoU standard are met. The relevant information against those criteria is also included in the PCNMR. The selected scope for the project activity is applicable.

## Project boundary, sources and RoUs

<b>Means of Project Verification</b>	Conducting remote inspections of the project site to assess the effluent treatment plant setup and its integration with the Gangamai Industries and Constructions Limited (GIACL). Document Review: Examining the project's documentation, including permits, ownership documents, flow details.
<b>Findings</b>	No findings raised
<b>Conclusion</b>	The project boundary is correctly defined in the PCNMR. The ETP is the project boundary in this project which treats the industrial wastewater by enhancing the water conservation and sustainability of the local water reserves.

## Baseline scenario of the water shed or activity prior to project commissioning

<b>Means of Project Verification</b>	As per the UWR scope 5 project the baseline scenario is as following: "The net quantity of treated ETP effluent / wastewater that would be discharged directly into the local drain/sewer without further being recycled and/or reused daily post treatment per year" Remote audit conducted and document review showed that in absence of the project activity, the waste water would have been directly discharged in the sewer without treating it and further contaminating the local water reserves.
<b>Findings</b>	No findings raised
<b>Conclusion</b>	The approved baseline methodology has been correctly applied to identify a realistic and credible baseline scenario, and the identified baseline scenario most reasonably represents what would occur in the absence of the proposed UWR project activity.  All the assumption and data used by the project participants are listed in the PCNMR and/or supporting documents. All documentation relevant for establishing the baseline scenario are correctly quoted and interpreted in the PCNMR. Assumptions and data used in the identification of the baseline scenario are justified appropriately, supported by evidence and can be deemed reasonable.

## Implementation Benefits to Water Security

<b>Means of Project Verification</b>	Examining the PCNMR, commissioning certificate, legal documentation and any other relevant documentation. By conducting interviews with the project proponent, owners. By assessing the water quality reports, as well as the impact of untreated water on local water reserves and quality testing was conducted by analyzing the quality of water post treatment.
<b>Findings</b>	No findings raised.
<b>Conclusion</b>	The Implementation Benefits to Water Security emphasizes the significant positive impact in safeguarding aquatic ecosystem in Dhora river and soil health. The project successfully significantly reduces the reliance on groundwater, a precious natural resource. By minimizing the demand for fresh water, GIACL can contribute to water conservation efforts and alleviate pressure on depleting aquifers. Overall, the project demonstrates effective strategies for reducing captive water consumption and responsibly managing groundwater, the project hopes to foster a broader adoption of environmentally responsible approaches within the industry.

❖ **Estimation of RoUs or net water saved/recycled/reused**

<b>Means of Project Verification</b>	<p>Remote inspection of the ETP unit to ensure it matches the project documentation. Examination of PCNMR, Commissioning Certificate, Project plan was carried out and other relevant documentation provided by the project proponent. Measurement Verification was carried out by checking the flow details.</p> <p>The net quantity of treated water used is measured via flow meters installed at the site. RoUs are calculated based on total quantity of treated water being recycled &amp; reused.</p> <p>RoU's achieved during the first monitoring period as per the Project Activity:</p> <table data-bbox="791 763 1251 1361"> <tr> <th>Year</th><th>Total ROUs (1000 liters)/yr UCR Cap(1 million RoUs/yr</th></tr> <tr><td>2014</td><td>44770</td></tr> <tr><td>2015</td><td>62240</td></tr> <tr><td>2016</td><td>59623</td></tr> <tr><td>2017</td><td>39514</td></tr> <tr><td>2018</td><td>81673</td></tr> <tr><td>2019</td><td>41807</td></tr> <tr><td>2020</td><td>38332</td></tr> <tr><td>2021</td><td>68295</td></tr> <tr><td>2022</td><td>72329</td></tr> <tr><td>2023</td><td>60552</td></tr> <tr> <td><b>Total RoUs</b></td><td><b>569,135</b></td></tr> </table> <p>The project is an ETP plant means the water budget component is surface inflow. According to the RoU Standard ver 7, PP has accounted 1% each as the uncertainty factor in inflow and outflow volumes to remain conservative. Therefore, an uncertainty factor of 0.98 is applied to all ROUs.</p>	Year	Total ROUs (1000 liters)/yr UCR Cap(1 million RoUs/yr	2014	44770	2015	62240	2016	59623	2017	39514	2018	81673	2019	41807	2020	38332	2021	68295	2022	72329	2023	60552	<b>Total RoUs</b>	<b>569,135</b>
Year	Total ROUs (1000 liters)/yr UCR Cap(1 million RoUs/yr																								
2014	44770																								
2015	62240																								
2016	59623																								
2017	39514																								
2018	81673																								
2019	41807																								
2020	38332																								
2021	68295																								
2022	72329																								
2023	60552																								
<b>Total RoUs</b>	<b>569,135</b>																								
<b>Findings</b>	<p>CL 03 and CAR 01 was raised and closed successfully. More information presented appendix below.</p>																								
<b>Conclusion</b>	<p>In summary, the calculation of RoU's was correctly demonstrated by the PP.</p> <p>It is confirmed by the assessment team that:</p> <p>For the estimation of Rainwater Offset Units (RoUs) or net water saved/recycled/reused at GIACL ETP, would highlight the successful implementation of a project activity that has effectively treated the industrial wastewater. The quantification tools and calculations detailed in the document indicate a total of 569,135 RoUs (1000 liters each) were collected over the monitoring period from 01/01/2014 to 31/12/2023. This initiative not only treated a significant amount of wastewater that would have otherwise gone untreated but also contributed to the improvement of Dhora river water quality,</p>																								

	demonstrating the project's positive impact on water security and sustainability in the region. The project serves as a model for similar industrial areas, showcasing the benefits of treating wastewater in enhancing in safeguarding the water quality of local water reserves.
--	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

### PCN+Monitoring Report

<b>Means of Project Verification</b>	Conducting off-site audit to verify the implementation and operation of the ETP. Examining all relevant documents, such as permits, ownership papers, and maintenance records of the ETP. Talking to the project proponent about the operation of the unit. Checking the accuracy of reported data, such as the flow details, flow meter details, treated water details and by evaluating the design and technical aspects of the ETP to ensure it aligns with the UWR RoU Standard principles.
<b>Findings</b>	CL 07 and CL 08 were raised and closed successfully. More information presented appendix below.
<b>Conclusion</b>	<p>The verification team is convinced of compliance of the monitoring plan. During the remote audit assessment, the verification team interviewed the PP that the monitoring arrangements described in the monitoring plan are feasible within the project design.</p> <p>The monitoring parameter reported in PCNMR adequately represents the parameters relevant to RoU calculation. The calibration report ensures the accuracy of the data reported. The number of RoU's generation is calculated based on this accurately reported data. The calculation was done using an excel sheet where all the parameters were reported. In the PCNMR RoU calculations are correctly calculated and reported. The PCNMR meets the requirements of UWR project verification requirements.</p>

### National Water Security Index

<b>Means of Project Verification</b>	As per UWR RoU standard version 7.0 all projects RoU methodology are ideally below the NWS score of 60 and NWSI equal or lower than 2 ( $NWSI \leq 2$ ). India's NWS score is below 60. This index is considered in establishing and implementing policies for sustainable water and groundwater development. As mentioned in the PCNMR, commissioning certificate and DPR this project is not a groundwater restoration project. It is an effluent treatment unit.
<b>Findings</b>	No findings raised
<b>Conclusion</b>	The verification team on assessment concluded that the project is an industrial wastewater recycle and reuse project and not a groundwater restoration project. Hence, national water security index is not applicable in this project.

### Start date, crediting period and duration

<b>Means of Project Verification</b>	The start date and crediting period of project activity was checked based on the commissioning certificate, PCNMR and other documents provided.
<b>Findings</b>	No findings raised.
<b>Conclusion</b>	The project has chosen crediting period start date as 01/01/2014. The crediting period is chosen as 01/01/2014 to 31/12/2023.

## Positive Environmental impacts

<b>Means of Project Verification</b>	PP has not claimed any separate positive environmental impact. The project being industrial wastewater treatment unit will reduce the further contamination of the local water reserves.
<b>Findings</b>	No findings raised
<b>Conclusion</b>	The project is a wastewater recycle/reuse project and reduces the further contamination of groundwater and local water reserves.

## Project Owner- Identification and communication

<b>Means of Project Verification</b>	PCNMR, communication agreement, commissioning certificate.
<b>Findings</b>	No findings raised
<b>Conclusion</b>	<p>The project owner was identified through a communication agreement signed between project owner and project aggregator. Commissioning certificate was also verified and they clearly establish the project ownership. The identification and communication correctly meet the requirement of project verification and UWR project standard.</p> <p>Project owner: Gangamai Industries and Constructions Limited (GIACL)</p>

## Positive Social Impact/Ecological Aspects/Recharge Aspects

<b>Means of Project Verification</b>	<p>Project has provided temporary employment to local people during its installation and commissioning. Also post commissioning some of people have employed permanently and local people were engaged leading to social financial benefit to surrounding. Overall social impact of project implementation is positive on the surrounding area.</p> <p>Also, The PP has showcased the successful wastewater treatment of industrial effluent, thus saving millions of liters of wastewater for the production of Leather.</p> <p>The project activity showcases best-in-class wastewater treatment technology that can replace the equivalent freshwater and industrial demand in different sectors for nonportable purposes while reducing the proportion of untreated wastewater and substantially increasing recycling and safe reuse in India.</p>
<b>Findings</b>	CL 05 and 06 were raised and closed successfully. More information presented appendix below.
<b>Conclusion</b>	Project has overall social positive impact and ecological positive impact

## Sustainable development aspects

<b>Means of Project Verification</b>	<p>PP has claimed SDG Goals 3, 4, 6, 8 &amp; 13.</p> <p>SDG 3 is good health and well-being and it is verified during remote audit. PP showcases how recycling and reusing wastewater can prevent depletion of natural water reserves and prevent water scarcity during droughts. The hazardous impact of industrial wastewater is avoided due to this project. This ensures water availability in water-scarce zones that help promotes healthy lives and well-being in the region.</p>
--------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



	<p>SDG 4 is Quality Education. During remote audit it was verified that the PP has provided School bus to the staff and children for better transportation.</p> <p>PP has installed smart tv in the nearest village school and constructed Classroom in nearest village.</p> <p>PP has conducted Educational &amp; Health Awareness for the employees and villagers.</p> <p>SDG 6 is sustainable development and is verified during remote audit. The project has showcased recycling and safe reuse of 563 cubic meter/day (0.563 MLD) which is the operational capacity of the plant and the actual installed capacity is 1000 cubic meter/day (1 MLD) within the industry during this monitoring period and the same was verified by the assessment team.</p> <p>SDG 8 is decent work &amp; economic growth and this was verified by the supporting document of employment details provided.</p> <p>SDG 13 is climate action. This was verified during the remote audit. PP recycles and reuses the industrial wastewater. Recycling and reusing wastewater is an effective solution for climate change adaptation because it helps mitigate the impacts of droughts, floods, and other extreme weather events that are becoming increasingly common due to climate change due to water scarcity.</p>
<b>Findings</b>	CAR 02 was raised and closed successfully. More information presented appendix below.
<b>Conclusion</b>	The project has the capability to address SDG 3, 4, 6, 8 and 13.

## ❖ Internal quality control

The verifier confirms that,

- Due professional care has been taken while reviewing the submitted document.
- There is no conflict of interest as the verifier has no other engagement with either the aggregator or project owner directly or indirectly.
- Verification team consists of experienced personnel.

## Project Verification opinion

Assessment team conducted documentation review the PCNMR against the UWR RoU verification standard version 2.0 and UWR RoU standard version 7.0 and the UWR-PCNMR FORM Version 3.0.

It is confirmed that the project activity is an industrial effluent treatment plant, that is located in Harinagar, Najik Babhulgaon, Post: Rakshi, Tal-Shevgaon, Dist: Ahmednagar in the state of Maharashtra, India. The geo co-ordinates of the plant have been mentioned in sections above. Assessment team performed an offsite audit and confirmed that the location described in the PCNMR is accurate. The verification was performed on the basis of UWR requirements, and host country criteria, as well as criteria given to provide for consistent project operations, monitoring and reporting.

The verification consisted of the following three phases: i) desk review of the PCNMR and additional background documents; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification report and opinion.

The project correctly applies the approved baseline and monitoring methodology.

The monitoring plan provides for the monitoring of the project's Rainwater Offset Unit (RoU) calculations. The monitoring arrangements described in the monitoring plan are feasible within the project design, and the project participants are able to implement the monitoring plan. Given that the project is implemented and maintained as designed, the project has achieved the RoU's of 569,135 RoU during the monitoring period i.e. from 01/01/2014 to 31/12/2023.

The review of the project design documentation and the subsequent follow-up interviews have provided assessment team with sufficient evidence to determine the fulfilment of stated criteria. In our opinion, the project meets all applicable UWR requirements. Assessment team thus requests the registration of the proposed UWR project activity.

## Appendix 1. Abbreviations

Abbreviations	Full texts
UWR	Universal Water Registry
PCNMR	Project Concept Note and Monitoring Report
NGO	Non-Governmental Organization
CAR	Corrective Action Request
CL	Clarification Request
ETP	Effluent Treatment Plant
RoU	Rainwater Offset Unit
DPR	Detailed Project Report

## Appendix 2. Competence of team members and technical reviewers

❖ Mr. Pankaj Kumar worked as team leader – Bihar for South Asia Climate Proofing and Growth Development (CPGD) – Climate Change Innovation Programme (CCIP) supported by DFID that seeks to mainstream climate change resilience into planning and budgeting at the national and sub-national level in India, Pakistan, Nepal, and Afghanistan. Pankaj Kumar has worked previously with IL&FS Infrastructure Development Corporation and BUIDCO (Bihar Urban Infrastructure Development Corporation), Govt. of Bihar as Environmental Specialist for WB & ADB funded projects. Prior to this, he worked with Carbon Check (UNFCCC accredited DoE), Johannesburg, RSA, Applus certification as Team Leader for validation, verification of around 100 GHG projects in Asia, Africa, USA, Asia Pacific & Americas. Pankaj is accredited Lead Auditor, Validator, Verifier and Technical Expert for Sectoral Scope/Technical Area – 1.1, 1.2, 3.1, 4.1, 13.1 by Enviance. He is also member of task force on climate change & human health, Health Department, GoB and on roster of UNICEF's WASH experts. He is an experienced, qualified and result oriented Environment Professional having more than 14 yrs. of relevant experience in Climate Change (Mitigation & Adaptation), Environmental Due Diligence, Disaster Risk Reduction, Validation and Verification of GHG project under CDM, Verified Carbon Standard, Gold Standard & Social Carbon Standard, Brazil. He provides technical support for environmental investigative, consultative and remedial projects involving air, water and soil, Waste management, EIA, Environmental Compliance, ISO 14001, OHSAS 18001, GHG accounting (ISO 14064) and Carbon foot printing. Pankaj Kumar is Masters in Environment Management from Forest Research Institute (University), I.C.F.R.E, Dehradun, which is Centre of Excellence in South East Asia for Forestry education & research and PGDEL from National Law School of India University, Bangalore (India).

❖ Vipul holds Bachelor of Technology from VIT University Vellore in 2020. He has gained valuable work experience as a site engineer at Light House Energy Developers, where he was employed from May 2020 to August 2022. Vipul holds an IRCA certification as an ISO 9001 Lead Auditor, demonstrating his expertise in quality management systems. He is well-versed in ISO 14064-1, ISO 14064-2, and ISO 14064-3, which are standards for greenhouse gas accounting and reporting. Furthermore, Vipul has received training in ISO 17029 and ISO 14065, highlighting his proficiency in environmental auditing and conformity assessment. He has also completed Clean Fuel Regulation training from Environment and Climate Change Canada, demonstrating his expertise in environmental management and sustainability.

❖ Ms. Swati Mahajan is graduate in Environmental Engineering from Shivaji University, India and previously worked as an Environment Engineer at Eco Designs India Private Ltd., Pune. She is adept in designing of landfill sites for solid waste management. She also has hands on experience in cost benefit analysis and preparation of DPRs for SWM projects. She also has done a certified

course in carbon capture and storage from Edinburg University. Currently working as GHG assessor for projects under various GHG mechanisms like GCC, ICR, UCR and VERRA.

❖ Mr. Vijayanand is an experienced professional, a strategic HSE expert with 16 years of leadership in environmental consulting, audit, and regulatory compliance. He has successfully implemented HSE/ESG rules across Asia and Europe, managing corporate and site-level HSE functions. His roles have involved EIA, waste management, and policy development. He is leading HSE and ESG efforts at Hero Future Energies, demonstrating budgeting, due diligence, and international standard implementation skills. He has contributed to impactful projects like ESIA, renewable energy initiatives, and audits. He is also having accreditation as a Lead Auditor in CDM and Verra by various DOEs/VVBs, he is qualified by Enviance as a TL, TR and Technical expert in Section 1.2, 3.1, 14.1.

### Appendix 3. Document reviewed or referenced

No.	Author	Title	References to the document	Provider
1	NA	Communication agreement		Project Owner
2	NA	Project Concept Note and Monitoring Report		Aggregator
3	NA	RoU Calculation sheet		Aggregator
4	NA	Declaration on avoidance of double counting		Aggregator
5	NA	Commissioning Certificates for the ETP		Aggregator
6	NA	Water flow details/log book details for the complete monitoring period		Aggregator
7	NA	Calibration certificates for water meters		Aggregator
8	UWR	UWR RoU Program manual version 2.0 UWR RoU standard version 7.0 UWR RoU Verification standard version 2 UWR terms and conditions		Universal Water Registry

### Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

Classification	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	01
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
PP shall update the section A.2 of PCNMR as per the UWR template of PCNMR version 3.0. Also, PP shall add section A.2.1			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
PP has corrected the section as per the UWR template pf PCNMR version 3.0. Also, PP shall add section A.2.1			
Validation/Verification Team Assessment		Date:	05/12/2024
PP has updated section A.2 and also added section A.2.1 as per the UWR template pf PCNMR version 3.0 and the same has been assessed in PCNMR version 2.0. Hence, this part of CL is closed.			

Classification	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	02
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
As per UWR RoU verification standard version 2.0, PP shall submit an undertaking for no double counting for current monitoring period and for project activity has neither been registered nor seeking registration under any other water registry or sustainable development programs.			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
PP has submitted the double Counting declaration for current monitoring period.			
Validation/Verification Team Assessment		Date:	05/12/2024
PP has submitted an undertaking for no double counting for current monitoring period and for project activity has neither been registered nor seeking registration under any other water registry or sustainable development programs and the same has been assessed by the verifier. Hence, this part of CL is closed.			

Classification	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	03
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
PP shall submit the supporting documents of few missing values of ETP inlet.			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
PP has submitted the supporting documents of inlet Missing data.			
Validation/Verification Team Assessment		Date:	05/12/2024
PP has submitted the supporting documents of ETP inlet missing data and the same has been assessed with the values mentioned in the excel sheet and are found to be consistent. Hence, this part of CL is closed.			

Classification	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	04
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
<div>1. PP shall submit the clear pictures of the meter, details of which are consistent with the submitted calibration certificate.</div> <div>2. As explained during the audit, client measures the ETP inlet water flow manually through a V notch. PP shall submit the details of the V notch and the same is to be added in PCNMR.</div>			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
<div>1.PP want to clarify that only one Flow meter has been installed in the outlet as that is tie up with MPCB. PP has already attached the meter photo with calibration certificate with serial no visible in the PCNMR.</div> <div>2. PP has included and submitted the details of V Notch in the PCNMR.</div>			
Validation/Verification Team Assessment		Date:	05/12/2024
<div>1. PP has submitted all the details of the flow meter which is installed at the outlet and the same has been verified by the assessment team. Hence, this part of CL is closed.</div> <div>2. PP has submitted the details of the V notch and the same has been added in PCNMR version 2.0. The details have been assessed by the verification team. Hence, this part of CL is closed.</div>			

<b>Classification</b>	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	<b>Number:</b>	05
<b>Raised by:</b>	Mr. Pankaj Kumar	<b>Document Reference</b>	PCNMR
<b>Finding Description</b>		<b>Date:</b>	29/11/2024
PP has claimed SDG goal 8. Supporting documents of the same should be submitted.			
<b>Client/Responsible Party/Project Proponent Response</b>		<b>Date:</b>	02/12/2024
PP has submitted the Supporting documents claimed SDG goal 8.			
<b>Validation/Verification Team Assessment</b>		<b>Date:</b>	05/12/2024
1. PP has submitted the employment details which satisfies the SDG goal 8. The details have been verified by the assessment team. Hence, this part of CL is closed.			

<b>Classification</b>	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	<b>Number:</b>	06
<b>Raised by:</b>	Mr. Pankaj Kumar	<b>Document Reference</b>	PCNMR
<b>Finding Description</b>		<b>Date:</b>	29/11/2024
PP shall submit the details of local stakeholder meetings. Supporting documents of any ongoing consultation with stakeholders and also the list of names of local stakeholder.			
<b>Client/Responsible Party/Project Proponent Response</b>		<b>Date:</b>	02/12/2024
PP has submitted the names of local stakeholder. They are the responsible for taking decision and resolve comments.			
<b>Validation/Verification Team Assessment</b>		<b>Date:</b>	05/12/2024
PP has submitted the details of local stakeholder and the same has been verified. Hence, this part of CL is closed.			

<b>Classification</b>	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	<b>Number:</b>	07
<b>Raised by:</b>	Mr. Pankaj Kumar	<b>Document Reference</b>	PCNMR
<b>Finding Description</b>		<b>Date:</b>	29/11/2024
PP shall submit the water quality report of both untreated and treated water which are mentioned in PCNMR.			
<b>Client/Responsible Party/Project Proponent Response</b>		<b>Date:</b>	02/12/2024
PP has already attached water quality report of both untreated and treated water which are mentioned in PCNMR (appendix).			
<b>Validation/Verification Team Assessment</b>		<b>Date:</b>	05/12/2024
1. PP has submitted the water quality report of both untreated and treated water and the same has been added in PCNMR version 2.0. The assessment team has verified the submitted supporting documents and have found consistent. Hence, this part of CL is closed.			

<b>Classification</b>	<input type="checkbox"/> CAR <input checked="" type="checkbox"/> CL/CR <input type="checkbox"/> FAR	<b>Number:</b>	08
<b>Raised by:</b>	Mr. Pankaj Kumar	<b>Document Reference</b>	PCNMR
<b>Finding Description</b>		<b>Date:</b>	29/11/2024

As discussed during the remote audit, the operational capacity of the plant is less than the actual capacity. PP shall clarify.		
<b>Client/Responsible Party/Project Proponent Response</b>	<b>Date:</b>	<b>02/12/2024</b>
PP wants to clarify that the Operational Capacity of the plant is 0.563 MLD as the effluent water generated is in tune of the same but has installed 1 MLD ETP to incorporate any further expansion plans.		
<b>Validation/Verification Team Assessment</b>	<b>Date:</b>	<b>05/12/2024</b>
PP has submitted the document which clarifies the operational capacity of the plant and the same has been added in PCNMR version 2.0. Assessment team has verified the documents and found to be consistent. Hence, this part of CL is closed.		

Table 2. CARs from this Project Verification

Classification	<input checked="" type="checkbox"/> CAR <input type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	01
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
In actual RoU's calculation excel sheet the values in column in F are hard quoted. PP shall the link the actual RoU's calculation column. (Column F) with the formula.			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
PP has added actual RoU's calculation column (Column F) with the formula.			
Validation/Verification Team Assessment		Date:	05/12/2024
In the submitted excel sheet PP has linked the actual RoU's calculation column (Column F) with the formula. Hence, this part of CAR is closed.			

Classification	<input checked="" type="checkbox"/> CAR <input type="checkbox"/> CL/CR <input type="checkbox"/> FAR	Number:	02
Raised by:	Mr. Pankaj Kumar	Document Reference	PCNMR
Finding Description		Date:	29/11/2024
SDG goals claimed on cover page and section A.9 are inconsistent. Correction sought.			
Client/Responsible Party/Project Proponent Response		Date:	02/12/2024
PP has corrected the section A.9 in the PCNMR.			
Validation/Verification Team Assessment		Date:	05/12/2024
PP has made corrections in the claimed SDG goals in section A.9 of PCNMR. The assessment team have verified the same in PCNMR version 2.0. Hence, this part of CAR is closed.			

Table 3. FARs from this Project Verification

<b>FAR ID</b>	xx	<b>Section no.</b>		<b>Date: DD/MM/YYYY</b>
<b>Description of FAR</b>				
<b>Project Owner's response</b>				<b>Date: DD/MM/YYYY</b>
<b>Documentation provided by Project Owner</b>				

<b>UWR Project Verifier assessment</b>	<b>Date: DD/MM/YYYY</b>